


# A Theory of Immersion Freezing


**Donifan Barahona**

Global Modelling and Assimilation office  
NASA Goddard Space Flight Center  
Greenbelt, MD, USA.


# Immersion Ice Nucleation



Soluble and  
Insoluble Aerosol  
Ice Nuclei (INP)  
Mostly dust, soot,  
and biological  
material



Immersion  
Freezing




**Ice crystal  
population**

- INP completely immersed
- Thermodynamic equilibrium
- Could happen at  $RH < 100\%$

- Determines phase partitioning in mixed-phase stratus and convective clouds
- Plays a very important role in the evolution of Arctic clouds
- May affect climate sensitivity (Tan et al. 2016).

# Classical Nucleation Theory




- Active site = adsorption site
- Water has uniform properties up to the dividing line
- Ice germ is implicitly considered denser than the liquid

## Vicinal Water Differs from Bulk Water


- **Vicinal water may exist in a ordered state (Ice-Like) near the solid-liquid interface** and that such ordered structures may propagate over hundreds to thousands of molecular diameters (Drost-Hansen, 1969, Zheng et al., 2006).
- Presence of ordered found in water near interfaces in biological (Snyder et al., 2014), metallic (Michot et al., 2002) and clay (Yu et al., 2001). Also supported by MD simulations (Cox et al., 2015).
- Strong evidence of ice formation several molecular diameters away from the clay-water interface: “ice formation does not require an ice germ attached to the substrate” (Anderson, 1967).
- The viscosity of interfacial water regulates the ice nucleation activity (Li et al., 2014). Increased viscosity may be a necessary condition for ice nucleation since structural ordering is not possible in a fluid with low viscosity (Anderson, 1967).
- **The work of nucleation and the enhancement of the viscosity of the vicinal water are tightly linked.**

# Nucleation within a Dense Liquid



1. Description of the properties of vicinal water
2. Relate vicinal water thermodynamics to the work of ice nucleation
3. Description of the effect of the particle on the interfacial flux, hence on the nucleation rate

# 1-Thermodynamics of Vicinal Water



$\zeta$  = Fraction of Ice-Like regions in the vicinal water (i.e., Templating Factor).


For homogeneous nucleation  $\zeta = 0$

Two state model: Regular solution of Liquid Like (LL) and Ice Like (IL) regions, in equilibrium with the bulk liquid

$$\mu_{vc} = \mu_w = \mu_{LL} + \zeta \Delta\mu_s - \frac{2k_B T_c}{N} \zeta(1 - \zeta).$$

$\Delta\mu_s$ : Free energy of fusion  
 $T_c, N$  = Critical parameters

## 2-Work of Nucleation




Nucleation modeled as occurring *Homogeneously* in the LL regions

$$\Delta G_{het}(a_w) = \Delta G_{hom}(a_{w,eff}).$$

# Homogeneous Ice Nucleation

Bulk liquid

$$\begin{matrix} N_w \\ \mu_{w,1} \end{matrix} \rightarrow \begin{matrix} \mu_{w,2} \\ N_w - n \end{matrix}$$



interface

$$\begin{matrix} \mu_{w,ls} \\ n_{ls} \end{matrix}$$

$\Delta h_f$ : Enthalpy of fusion

$a_w$ : Water activity

$\Gamma_w$ : Interface thickness (1.46)

$s$ : Lattice geometry (1.105)


- Neg-entropic Nucleation Framework, NNF:
  - Emphasizes entropic changes across the interface.
  - Obviates the explicit parameterization of the interfacial energy and the activation energy.
  - Accounts for *dissipation* effects during ice germ formation

$$\Delta G_{\text{nuc}} = \frac{4}{27} \frac{[\Gamma_w s (\Delta h_f - \Gamma_w k_B T \ln a_w)]^3}{[k_B T \ln \left( \frac{a_w^2}{a_{w,\text{eq}}} \right)]^2}.$$

$$\Delta G_{\text{act}} = k_B T \left[ \frac{E}{(T - T_0)} + n_t \ln \left( \frac{a_w}{a_{w,\text{eq}}} \right) \right].$$




# Work of nucleation: Spinodal Regime



$\zeta = 0$ ,  
Homogeneous  
nucleation


## Work of nucleation: Spinodal Regime



Particles with  $\zeta > 0.7$  may display spinodal behavior for immersion freezing  $T$

Spinodal point moves towards higher  $T$  for  $\zeta > 0$

### 3-Dynamics Of Ice Germ Growth



$$D \propto \exp\left(-\frac{A}{TS_c}\right)$$


Adam and Gibbs, 1965

The presence of the particle decreases the diffusivity of interfacial water by reducing the configurational entropy:

Only water in LL regions can diffuse


**INP that efficiently reduce the work of nucleation ( $\zeta > 0.7$ ) also tend to decrease the molecular flux to the ice germ**

# Nucleation rate: Dynamic and Thermodynamic Factors




**Classical regime ( $\zeta < 0.6$ ): High  $\Delta G$ , and high  $J_0$ . Limited effect of the particle on vicinal water. Steep  $dJ/dT$ .**

# Nucleation rate: Dynamic and Thermodynamic Factors



## Nucleation rate: Dynamic and Thermodynamic Factors




Two very different INP can display the same freezing temperature with very different sensitivities to cooling rate and surface area

Spinodal regime ( $\zeta < 0.7$ ): Negligible  $\Delta G$ , and low  $J_0$ . Strong kinetic limitations.

Shallow  $dJ/dT$

# Application: Immersion Freezing by Humic INP



Markers: Data from Rigg et al (2013).  $\Delta a_{w,het} = 0.2466 \pm 0.025$

Shaded area: Model predictions for  $a_w = 0.86$ ,  $0.91$ , and  $1.0$ .


$\zeta \sim 0.05$ . Classical germ forming regime.

Reasonable agreement in  $J_{het}$  but  $dJ_{het}/dT$  seems off.

$$\zeta^2 - \zeta \left( 1 - \frac{\Delta a_{w,hom}}{\Lambda_E} \right) - \left( \frac{\Delta a_{w,hom} - \Delta a_{w,het}}{\Lambda_E} \right) = 0.$$

Thermodynamic correspondence between  $\zeta$  and  $\Delta a_{w,het}$

# Spinodal Ice Nucleation



Markers: Data from Rigg et al (2013).  $\Delta a_{w,het} = 0.2466 \pm 0.025$

Shaded area: Model predictions for  $a_w = 0.86$ ,  $0.91$ , and  $1.0$ .


**Better agreement in  $dJ_{het}/dT$ .**

**Dynamical effects may play a significant role in this case.**

Find  $\zeta$  fitted in a region corresponding to spinodal ice nucleation to ( $\zeta \sim 0.955$ ).



# Spinodal Ice Nucleation may be Common



**Blue Lines: Classical regime**

**Red Lines: Spinodal regime**

**Markers: Derived and measured ice nucleation rates**


## Conclusions

- Current immersion freezing theory relies on a view that mimics ice formation from the vapor, neglecting several **interactions unique to the liquid**. A comprehensive approach is developed to account for such interactions.
- Instead of being purely driven by thermodynamics, heterogeneous ice nucleation in the liquid phase is a process determined by the **competition between thermodynamic and kinetic constraints** to the formation and propagation of ice.
- Accounting for the effect on the particle of the vicinal water suggests the **existence of a spinodal regime where dynamics controls the ice nucleation rate**. Preliminary data suggest that it may be common in nature.
- Paper under discussion: “On the Thermodynamic and Dynamic Aspects of Immersion Ice Nucleation”. ACPD.



**THANKS!**

# Water Activity Criterion



**Direct correspondence between  $\zeta$  and  $\Delta a_{w,hets}$**